BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Name of work: Providing water supply lines and facilites in Ward No. 08, Kodigehalli sub division.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	7	Supplying and delivery of brand new best make non return valve of size 50mm as per 15:778/84 with amendments with ISI mark etc., complete and as per the directions of the Engineer-in-charge of the work	Each	998.00	
2	7	Supplying and delivery of brand new best make gate wheel of size 50mm as per 15:778/84 with amendments with ISI mark etc., complete and as per the directions of the Engineer-in-charge of the work	Rmtr	1492.00	
3	16	Providing and fixing of 50mm G I bend to the motor etc., complete and as per the directions of the Engineer-in-charge of the work	Rmtr	220.00	
4	8	Providing and fixing of 50mm G I Nipple to the motor etc., complete and as per the directions of the Engineer-in-charge of the work	Mtrs	80.00	
5	8	Providing and fixing of 50mm G I Union to the motor etc., complete and as per the directions of the Engineer-in-charge of the work	Mtrs	450.00	
6	8	Providing and fixing Gun Metal Gate Wheel valve confirming to ISI specification of approved make as per drawing etc., complete and as per the directions of the Engineer-in-charge of the work	Each	887.25	
7	617.65 619.31	Earthwork excavation for foundation of buildings water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods etc., complete and as per the directions of the Engineer-in-charge of the work	cum	202.00	
8	1525.00 1550	Providing and installing at site of work P.V.C pipees including cost of pipes and specials and labour including lowering into trenches, laying true to line, level and perfect linking at joints leak proof including jointing of approved type with all labour and lift charges, handling charges including encasing the pipe alround to a depth not leass than 15 cms with gravel or selected earth available from the excavation etc., complete PVC pipes of 6kg/Sqm 75mm Dia.etc., complete and as per the directions of the Engineer-in-charge of the work	Rmtr	117.00	

ಕಾ.ಅ. (ಬ್ಯಾ.ವ)

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
9	285.00	Providing and installing at site of work 50 mm G.I pipees including cost of pipes and specials and labour including lowering into trenches, laying true to line, level and perfect linking at joints leak proof including jointing of approved type with all labour etc., complete and as per the directions of the Engineer-in-charge of the work		275.00	
10	617.65 542.0	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. and lift upto 1.5m. Including etc., complete and as per the directions of the Engineer-in-charge of the work	cum	65.00	

Signture of the Contractor

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

Assistant Executive Engineer
Byatarayanapura Sub-division
KRIDL, BBMP, Bangalore

ಕರಡು ಟೆಂಡರ್ ಷರತ್ತುಗಳನ್ನು
ತಿದ್ದುಪಡಿಗಳ ಸಂಖ್ಯೆ.....(3) Three.
ತಿದ್ದುಪಡಿ ಮಾಡಿ/ಇಲ್ಲದೆ
ಅನುಮೋದನೆ ನೀಡಿಲಾಗಿದೆ

ಅಧೀಕ್ಷಕ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ವಲಯ
ಬಿಬಿಎಂಪಿ, ಬೆಂಗಳೂರು-92